

Status of KM3NeT ARCA & ORCA


**Astroparticle and Oscillation
Research with Cosmics in the Abyss**

(Same technology for different goals)



KM3NeT DOMs and DUs

- 31 PMTs installed in 17" Digital Optical Modules (DOMs)
- 18 DOMs (Digital Optical Modules) on each Detection Unit (DU), spaced by ~36 m or ~9 m (in ARCA or ORCA layout, resp.)
- DUs placed at distances of ~90 m and ~20 m, resp. for ARCA and ORCA
- Same DOMs but different DUs (as to mechanical layout and adaptation to different infrastructures) used in ARCA and ORCA




More on Digital Optical Modules

- 31 PMTs of 3" photocathode in a 17" glass sphere
- Optical gel coupling between PMTs and glass
- Reflection rings around the PMTs to increase detection surface
- Electronics, optics for long-range communications and calibration devices (including: 'nanobeacon' LED pulser, compass/tiltmeter, and piezo-sensor for acoustic measurements) installed inside the sphere – each DOM acting as an individual, autonomous detection node
- Connection to the rest of the apparatus requires two conductors (+12 V power) and one optical fibre through a single penetrator




DU mechanics

- Mechanical structure of the string is based on two dyneema ropes, anchored on the sea floor and kept taut by a top buoy (plus DOM buoyancy)
 - Slender and strong arrangement
 - DOMs keep the correct attitude
 - String dynamics under control
- A backbone (VEOC - Vertical Electrical-Optical Cable) connects all DOMs to the DU base module – the VEOC is built on an oil-filled pressure-balanced hose
- DOM collars allow the DOMs to be fixed to the ropes
- Break-out-boxes (BOBs) allow connections of consecutive segments of VEOC and a DOM (or base module)
 - A BOB hosts all needed fibre splices and a DC/DC converter
 - A short cable (BEOC – BOB Electrical-Optical Cable) connects the BOB to the DOM penetrator (2 conductors and 1 fiber needed)



DOM and ropes




(ARCA) DU




DU installation

- DU is packed on a launcher vehicle (LOM) and installed on the anchor
- After deployment on sea bed and connection to the infrastructure, unfurling is done by operating a release mechanism (either acoustic or ROV-operable)
- LOM (and acoustic release as well, if applicable) is recovered after unfurling



ROV inspection of an unfurled DU



Deployment campaign of Dec. 2015 (ARCA-DU1)



DU deployment



Unfurling!




Phase-1 vs. Phase-2

Phase-1 (ongoing):


- 24 ARCA DUs at KM3NeT-It
- 6 ORCA DUs at KM3NeT-Fr

Phase-2 (coming up possibly soon!):

- 2 ARCA blocks at KM3NeT-It
- 1 ORCA block at KM3NeT-Fr (1 block = 115 DUs)



ORCA layout



ARCA layout

Phase-1

2 DUs deployed



Infrastructure at KM3NeT-Fr

- Shore station set up
- Long distance cable and Phase-1 node reinstalled (NEW!)
- Status: ready to connection of first DU!



Power hut(s)
at La Seyne sur mer



The node ready to board the
deployment ship




Overboarding!



Infrastructure at KM3NeT-It

- Shore station set up
- One of the 2 Junction Boxes needed for Phase-1 installed
- Status: 2 DUs in operation



ARCA-DU1 on sea bed
(Dec. 2015)



Underwater connection
of ARCA-DU1



The shore station
at Portopalo di Capo Passero



Preparing to deploy ARCA-DU2
and ARCA-DU3 (May 2016)



Junction Box (July 2016)




Development plan

Validation of the LOM unfurling concept




Sea qualification of connection tool



PPM DU



ARCA-DU1



ORCA Sea qualification



Dec09

Feb.11

Apr.13

Feb.14

May14

Jun.14

Dec.14


Dec.15

Mar.16

Deployment PPM DOM



Mechanical tests I



Mechanical tests II



DOM « 0 »



BUT:



May2016
ARCA-DU2
ARCA-DU3

ARCA-DU3

DU installed in May together with ARCA-DU2

Problem on one DOM noticed at the underwater test prior to unfurling – rest of the DU was operational

BUT... power short detected after unfurling

Symptoms not conclusive for understanding the problems; hence the DU was recovered

Remark: recovery was not a planned option – check the TDR:

Maintenance


Following unfurling no maintenance of detection units is planned. When predicting the global performance of the detector, account must be taken of the probability that parts - storeys or optical modules - will become blind. The power and data network must be designed in such a way that in no case can the failure of a detection unit propagate to another part of the detector.

Hence an extra-effort was needed for a detailed preparation



ARCA-DU3: the story of a summer


- ARCA-DU3 was recovered at end of July (2.5 months after deployment)
- Recovery is performed by pulling up the anchor – orientation of the DU monitored during recovery (transponder on HLL on anchor + beacon installed on top buoy)
- First round of tests in Malta, then autopsy at Nikhef
- All problems understood (see next slide)



Recovery of a DOM



Top of DU at sea
(hint: there are 3 DOMs in the picture!)



Start of recovery (anchor pulled up)



Beacon installed on top buoy








Anchor onboard




Outcome of ARCA-DU3 investigations

Failure of ARCA-DU3 was due to a lethal combination of factors (each of which possibly not fatal if taken individually) – a detailed report is under finalization (to be submitted to the STAC and RRB next week)

Strong points (confirmed):

-  Layout and mechanics of the DU
-  DU integration (including fiber treatment at all levels)
-  Installation (including transportation, unfurling)
-  Base module
-  DOMs (minor corrections needed)

Weak points (to be improved):

-  Design of some parts (mechanical and electronic) of VEOC
-  Integration and test of VEOC
-  Minor changes to DOM integration and test


Next:

- Define all needed corrective/preventive actions (as part of all other actions already planned, such as reviews – see next)
- Assess status of already available components (vital input for production of new DUs on a short term, such as ORCA-DU1, and for deciding about the good, old "DU1")
- Assess status of DUs already deployed


Quoted from our action plan: *"The approach is that the schedule of next deployment of detection units should not compromise the quality of the detection units"*




Selected results from ARCA-DU1&2




Nanobeacon-induced hits in DOMs (light emitted from DOM1 upwards)



Depth dependence of multiple-hit coincidence rates



Comparison of time offsets determined with different methods




A muon track detected by the two DUs



KM3NeT Phase-1 Infrastructure (Sept. 2016):

- 3 Installation sites
- 2 PMT preparation sites
- 4 DOM integration sites
- 3 DOM integration sites planned / in preparation
- 3 base module integration sites
- 3 DU integration sites
- 3 DU test and preparation to deployment sites
- 1 DU integration site planned



Status & conclusions

- Letter of Intent for ARCA and ORCA published Jan. 2016
- KM3NeT back in the ESFRI roadmap!
- Possibility that funding becomes available soon to extend Phase-1 into Phase-2!
- Finalization of return of experience of ARCA-DU3 and of review of the project needed before launching massive construction of DUs
- Setting up structures which can build DUs at a speed ~2-3 DUs/month (adequate for Phase-1, to be further increased for Phase-2)
- Data taking started (2 DUs) for ARCA at KM3NeT-It!
- Considering when to deploy first ORCA DU at KM3NeT-Fr

